Section 1 - Survey Details ◀ Back

Address of Survey

UPRN:

Address & Postcode:

Chapel End School

, WN5 7TX

Client Details

Client Name:

Address & Postcode:

STHMBC

5th Floor Wesley House, Corporation Street,

, WA10 1HF

Name and Address of Organisation

Name:

Address & Postcode:

Telephone Number:

Email:

Website:

UKAS Reference Number:

The Testing Lab PLC

Unit 2 James Road, Adwick-le-Street,

Doncaster, DN6 7HH

08001 777264

info@thetestinglab.eu

www.thetestinglab.eu

7758

Survey Information

TTL Job No:

Date of Survey:

Date of Report:

J209920

16/08/2022

26/08/2022

Document Authorisation

L. Simpson

Ian Greenan

Lead Surveyor

Louise Simpson

Quality Checked

Section 2 - Executive Summary ◀ Back

Scope, Type and Extent of Survey

The scope of this survey was to attend site and carry out a Management Asbestos Survey to the property known as Chapel End School . Care MUST be taken to read the site-specific information in Section 3. The area was temporarily vacant whilst the survey was undertaken. During the inspection, information was to be collated and recorded about the location and condition of asbestos containing materials and this information was to be used to carry out a risk assessment for each individual occurrence. The results of the risk assessments will be used to compile the asbestos management plan. This report relates ONLY to the specific building depicted on the front cover and should not be reproduced without the permission of the producer.

Please note that material risk assessments (MRA) are collected as standard; priority risk assessments (PRA) are collected at the clients request and are not covered within the scope of TTL's UKAS accreditation.

Should any suspect material be uncovered after this report has been issued, The Testing Lab PLC MUST be contacted in the first instance and shown the material in situ, to verify the said materials prior to any subsequent remedial action. No liability will be accepted for remedial works which have not been verified by The Testing Lab PLC.

Site Specific Location & Summary of ACMs and Risk Scores

Below is a summary chart showing the locations of all of the components which have been identified as an asbestos containing material. ACMs with high scores are highlighted in red. For the individual material assessments, please refer to Section 5 – Pictures and Risk Scores of Individual Occurrences. For drawings depicting the exact location of the inspected component please see Section 5 – Marked-Up Plans.

Summary of ACMs ◀ Back

Record ID	As	Survey Type	Location	Product Type	Qty	Accessibility	Condition	Surface Treatment	Asbestos Type	Means of Identification	Material Risk	Priority	Action
<u>▶ \$001</u>		Management	Main, Ground, 001 Main Entrance Lobby, Ceiling, Textured Coating To Ceiling	Textured Coating	8 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Chrysotile	The Testing Lab PLC	3 (VL)	N/A	Manage
<u>▶5004</u>	(S001)	Management	Main, Ground, 002 & 003 School Office, Ceiling, Textured Coating To Ceiling	Textured Coating	16 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>▶ S006</u>	(S001)	Management	Main, Ground, 004 Corridor, Ceiling, Textured Coating To Ceiling	Textured Coating	20 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>▶</u> \$009		Management	Main, Ground, 004 Corridor, Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	20 Sqr Mtrs	Difficult	Good condition: no visible damage.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Chrysotile	The Testing Lab PLC		N/A	Manage
<u>▶ 5010</u>		Management	Main, Ground, 006 Switch Room 1, Ceiling,	Textured Coating	4 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Chrysotile	The Testing Lab PLC	3 (VL)	N/A	Manage

													STHMBO
			Textured Coating To Ceiling										
<u>> S012</u>	(\$009)	Management	Main, Ground, 006 Switch Room 1, Floor, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	4 Sqr Mtrs	Easy	Good condition: no visible damage.	containing asbestos:	Strongly Presumed Chrysotile	In-House Database	2 (VL)		Manage
<u>> 5014</u>	(S010)	Management	Main, Ground, 005 Infants Hall, Celling, Textured Coating To Ceiling	Textured Coating	120 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>> S016</u>		Management	Main, Ground, 005 Infants Hall, Floor, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	110 Sqr Mtrs	Easy	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Chrysotile	The Testing Lab PLC	3 (VL)	N/A	Manage
<u>> S017</u>	(5010)	Management	Main, Ground, 009 PE Store, Ceiling, Textured Coating To Ceiling	Textured Coating	10 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>> 5019</u>	(S016)	Management	Main, Ground, 009 PE Store, Floor, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	10 Sqr Mtrs	Easy	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)		Manage
►S020		Management	Main, Ground, 010 Resourse Area, Ceiling,	Textured Coating	300 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl	Chrysotile	The Testing Lab PLC	3 (VL)	N/A	Manage

J209920 - Page 6 of 147

													STHMB
			Textured Coating To Ceiling					tiles, semi rigid paints or decorative finishes.					
<u>S022</u>	(S009)	Management	Main, Ground, 010 Resource Area, Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	300 Sqr Mtrs	Difficult		containing asbestos:	Strongly Presumed Chrysotile	In-House Database	2 (VL)	N/A	Manage
<u>S024</u>	(SO20)	Management	Main, Ground, 010A Art Store, Ceiling, Textured Coating To Ceiling	Textured Coating	3 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>> S026</u>		Management	Main, Ground, 010A Art Store, Below Floor Covering, Floor Tile Adhesive Only	Bitumen Product	3 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Chrysotile	The Testing Lab PLC	3 (VL)	N/A	Manage
<u>> 5027</u>	(SO2O)	Management	Main, Ground, 011 Classroom, Ceiling, Textured Coating To Ceiling	Textured Coating	40 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)		Manage
<u>▶ S029</u>	(SO26)	Management	Main, Ground, 011 Classroom, Below Floor Covering, Floor Tile Adhesive Only	Bitumen Product	40 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage

J209920 - Page 7 of 147

													STHMBO
<u>S030</u>	(5020)	Management	Main, Ground, 012 Cleaners Cupboard, Ceiling, Textured Coating To Ceiling	Textured Coating	2 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
► S032	(5009)	Management	Main, Ground, 012 Cleaners Cupboard, Floor, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	2 Sqr Mtrs	Easy	Good condition: no visible damage.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	2 (VL)	N/A	Manage
►S033	(5020)	Management	Main, Ground, 013 Girls Tollets, Ceiling, Textured Coating To Ceiling	Textured Coating	6 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>► \$037</u>	(5020)	Management	Main, Ground, 014 Cloaks, Ceiling, Textured Coating To Ceiling	Textured Coating	6 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
▶ \$040	(5020)	Management		Textured Coating	50 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>► S044</u>	(SO20)	Management		Textured Coating	6 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage

MQF3177a Issue 6 05/2022

													STHIVIB
			Textured Coating To Ceiling					tiles, semi rigid paints or decorative finishes.					
<u>S048</u>	(5020)	Management	Main, Ground, 018 Classroom, Ceiling, Textured Coating To Ceiling	Textured Coating	50 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	containing asbestos:	Strongly Presumed Chrysotile	In-House Database		N/A	Manage
<u>► S051</u>	(SO20)	Management	Main, Ground, 019 Cloaks, Ceiling, Textured Coating To Ceiling	Textured Coating	6 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	containing asbestos:	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>► S054</u>	(5020)	Management	Main, Ground, 020 Girls Toilets, Ceiling, Textured Coating To Ceiling	Textured Coating	6 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database		N/A	Manage
► S058	(SO20)	Management	Main, Ground, 021 Classroom, Ceiling, Textured Coating To Ceiling	Textured Coating	50 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)		Manage
<u>▶ \$060</u>	(SO20)	Management	Main, Ground, 022 Boys Toilets, Ceiling, Textured Coating To Ceiling	Textured Coating	6 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage

J209920 - Page **9** of **147**

												-	STHMBO
<u>> S063</u>	(S020)	Management	Main, Ground, 023 Cloaks, Ceiling, Textured Coating To Ceiling	Textured Coating	6 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.		Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
▶ \$066	(SO20)	Management	Main, Ground, 024 Classroom, Ceiling, Textured Coating To Ceiling	Textured Coating	50 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>▶ 5070</u>	(5020)	Management	Main, Ground, 027 Girls Tollets, Ceiling, Textured Coating To	Textured Coating	6 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>▶ 5074</u>	(SO20)	Management	Main, Ground, 028 Classroom, Ceiling, Textured Coating To Ceiling	Textured Coating	50 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>► \$079</u>	(5001)	Management	Main, Ground, 030 Head Teachers Office, Ceiling, Textured Coating To Ceiling	Textured Coating	16 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>▶ S081</u>	(\$026)	Management	Main, Ground,	Bitumen Product	16 Sqr Mtrs	Difficult	Low damage: a few scratches or surface	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage

J209920 - Page **10** of **147**

													STHMBC
			030 Head Teachers Office, Below Floor Covering, Floor Tile Adhesive Only				marks, broken edges on boards, tiles etc.	tiles, semi rigid paints or decorative finishes.					
<u>► \$082</u>	(5001)	Management	Main, Ground, 031 Staff Room, Ceiling, Textured Coating To Ceiling	Textured Coating	50 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>▶ S092</u>	(\$009)	Management	Main, Ground, 033 Store Room, Floor, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	4 Sqr Mtrs	Easy	Good condition: no visible damage.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	2 (VL)	N/A	Manage
<u>▶5095</u>		Management	Main, Ground, 034 First Aid Room, Cistern & Seat, Cistern & Seat	Plastic	1 Num	Easy	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Amosite	The Testing Lab PLC	4 (VL)	N/A	Manage
▶ 5099	(5001)	Management	Main, Ground, 076 Reprographics , Ceiling, Textured Coating To Ceiling	Textured Coating	16 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>▶\$107</u>		Management	Main, Ground, 075 PE Store, Floor, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	16 Sqr Mtrs	Easy	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Chrysotile	The Testing Lab PLC	3 (VL)	N/A	Manage

MQF3177a Issue 6 05/2022

									Cl	The Treation	2 (1) (1)	11/4	Manage
<u>▶\$110</u>			Main, Ground, 037 Servery / Chair Store, Sink Pad, Sink Pad	Bitumen Product		Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Chrysotile	The Testing Lab PLC		N/A	Manage
<u>▶S116</u>		Management	Main, Ground, 038 Kitchen , Table, Bitumen Paint	Bitumen Product	2 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Chrysotile	The Testing Lab PLC	3 (VL)	N/A	Manage
<u>▶\$146</u>		Management	Main, Ground, 055 Classroom, Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	60 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Chrysotile	The Testing Lab PLC	3 (VL)		Manage
►S152	(5146)	Management	Main, Ground, 057 & 058 Classroom Store, Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	1 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)		Manage
<u>▶ \$155</u>	(5146)	Management	Main, Ground, 059 Classroom, Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	60 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>▶ \$158</u>	(S146)	Management	Main, Ground, 060 Classroom Store, Below Floor Covering,	Thermo Plastic Floor Tiles	1 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage

1209920 - Page 12 of 147

													STHMB
			Floor Tiles & Adhesive										
<u>► \$178</u>	(5146)	Management	Main, Ground, 068 Classroom, Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)		Manage
<u>► S181</u>	(\$146)	Management	Main, Ground, 069 Classroom Store, Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	1 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	containing asbestos:	Strongly Presumed Chrysotile	In-House Database	3 (VL)		Manage
<u>► \$184</u>	(\$146)	Management	Main, Ground, 070 Classroom Store, Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	1 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
►S187	(\$146)	Management	Main, Ground, 071 Classroom, Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	60 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.		In-House Database		N/A	Manage
►S204		Management	Main, Ground, N001 Cloakroom, Ceiling, Textured Coating To Ceiling	Textured Coating	10 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos; reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Chrysotile	The Testing Lab PLC	3 (VL)	N/A	Manage

J209920 - Page 13 of 147

											_		SIHMRC
<u>▶</u> \$207	(5204)	Management	Main, Ground, N001A Disabled Tollet, Celling, Textured Coating To Ceiling	Textured Coating	7 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)		Manage
►S210	(\$204)	Management	Main, Ground, N002 Nursery Classroom, Celling, Textured Coating To Celling	Textured Coating	Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)		Manage
► S217	(5204)	Management	Main, Ground, N007 Laundry , Ceiling, Textured Coating To Ceiling	Textured Coating	7 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database		N/A	Manage
<u>▶S220</u>	(\$204)	Management	Main, Ground, N007A Laundry Store, Ceiling, Textured Coating To Ceiling		1 Sqr Mtrs		Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
►S239		Management	Main, First, 106 Classroom Store , Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	1 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Chrysotile	The Testing Lab PLC	3 (VL)	N/A	Manage

MQF3177a Issue 6 05/2022

J209920-26/08/2022

S242	(S239)	Management	Main,	Thermo Plastic Floor	60 Sqr	Difficult	Low damage: a few	Composite materials	Strongly	In-House	3 (VL)	N/A	Manage
3242	(3233)	ivianagement	First, 107 Classroom, Below Floor Covering, Floor Tiles &		Mtrs		scratches or surface marks, broken edges on boards, tiles etc.	containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Presumed Chrysotile	Database			
<u>> S245</u>	(5239)	Management	Adhesive Main, First, 108 Classroom, Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	60 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
►S271	(5239)	Management	Main,	Thermo Plastic Floor Tiles	60 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing as bestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>S275</u>	(5239)	Management	Main, First, 121 Classroom, Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	60 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing as bestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>> S278</u>	(S239)	Management	Main, First, 122 Classroom Store, Below Floor Covering, Floor Tiles & Adhesive	Thermo Plastic Floor Tiles	1 Sqr Mtrs	Difficult	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl tiles, semi rigid paints or decorative finishes.	Strongly Presumed Chrysotile	In-House Database	3 (VL)	N/A	Manage
<u>> \$285</u>		Management	Main, Ground,	Textured Coating	2 Sqr Mtrs	Medium	Medium damage: significant breakage or materials or several small areas where	Composite materials containing asbestos: reinforced plastics, resins, mastics, vinyl	Chrysotile	The Testing Lab PLC	4 (VL)	N/A	Encapsula e/Repair

J209920 - Page 15 of 147

			007 Gas Meter Cupboard , Ceiling, Textured Coating To Ceiling				material has been damaged revealing loose asbestos fibres.	tiles, semi rigid paints or decorative finishes.					
<u>▶ 5287</u>	(\$285)	Management	Main, Ground, 008 Boiler Room, Ceiling, Textured Coating To Ceiling	Textured Coating	20 Sqr Mtrs		Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	containing asbestos:	Strongly Presumed Chrysotile	In-House Database			Manage
<u>▶\$295</u>		Management	Main, Ground, 047 Main Switch Room, Cable Wrap, Cable Wrap	Textiles	1 Num	Medium	Good condition: no visible damage.	Enclosed sprays and lagging, AIB (with exposed face painted or encapsulated) asbestos cement sheets.	Strongly Presumed Crocidolite Amosite	In-House Database			Manage
<u>►S297</u>		Management	Main, Ground, 049 Boiler Room 2, Ceiling, Ceiling	Cement	15 Sqr Mtrs	Medium	Low damage: a few scratches or surface marks, broken edges on boards, tiles etc.	Enclosed sprays and lagging, AIB (with exposed face painted or encapsulated) asbestos cement sheets.	Chrysotile	The Testing Lab PLC	4 (VL)	N/A	Encapsulat e and Label

MQF3177a Issue 6 05/2022

Summary of Non-Suspect or NADIS Items ◀ Back

The table below depicts items which were assessed but were either non-suspect or NADIS. Other components may have been looked at but are not listed due to the nature of the component and obvious common knowledge. If in doubt about a component please call The Testing Lab on 08001 777264.

Record ID	Survey Type	Location	Sample Ref	Qty	Action
►S003	Management	Main, Ground, 001 Main Entrance Lobby, Walls & Floor, Walls & Floor		Num	No further action required
► S005	Management	Main, Ground, 002 & 003 School Office, Walls & Floor, Walls & Floor		Num	No further action required
►S008	Management	Main, Ground, 004 Corridor, Walls Internal, Walls Internal		Num	No further action required
▶ S011	Management	Main, Ground, 006 Switch Room 1, Walls Internal, Walls Internal		Num	No further action required
▶ 5013	Management	Main, Ground, 006 Switch Room 1, Electrics, Electrics		Num	No further action required
▶ 5015	Management	Main, Ground, 005 Infants Hall, Walls Internal, Walls Internal		Num	No further action required
<u>▶5018</u>	Management	Main, Ground, 009 PE Store, Walls Internal, Walls Internal		Num	No further action required
<u>►S021</u>	Management	Main, Ground, 010 Resource Area, Walls Internal, Walls Internal		Num	No further action required
<u>►S023</u>	Management	Main, Ground, 010 Resource Area, Electrics, Electrics		Num	No further action required
►S025	Management	Main, Ground, 010A Art Store, Walls Internal, Walls Internal		Num	No further action required
<u>►S028</u>	Management	Main, Ground, 011 Classroom, Walls Internal, Walls Internal		Num	No further action required
<u>▶S031</u>	Management	Main, Ground, 012 Cleaners Cupboard, Walls Internal, Walls Internal		Num	No further action required
▶ 5034	Management	Main, Ground, 013 Girls Toilets, Walls Internal, Walls Internal		Num	No further action required

J209920 - Page 17 of 147

1209920-26/08/2022 STHMBC

<u>► 5036</u>	Management	Main, Ground, 013 Girls Toilets, Toilet Seat, Toilet Seat	5036	3 Num	No Further Action Required
► S038	Management	Main, Ground, 014 Cloaks, Walls Internal, Walls Internal		Num	No further action required
►S041	Management	Main, Ground, 015 Classroom, Walls & Floor, Walls & Floor		Num	No further action required
<u>► \$043</u>	Management	Main, Ground, D16 Covered Play Area, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
<u>➤ S045</u>	Management	Main, Ground, 017 Boys Toilets, Walls Internal, Walls Internal		Num	No further action required
▶ 5047	Management	Main, Ground, 017 Boys Toilets, Toilet Seat, Toilet Seat	(As S036)	3 Num	No Further Action Required
► S049	Management	Main, Ground, 018 Classroom, Walls & Floor, Walls & Floor		Num	No further action required
<u>➤ S052</u>	Management	Main, Ground, 019 Cloaks, Walls Internal, Walls Internal		Num	No further action required
<u>► \$055</u>	Management	Main, Ground, 020 Girls Toilets, Walls Internal, Walls Internal		Num	No further action required
<u>►5057</u>	Management	Main, Ground, 020 Girls Toilets, Toilet Seat, Toilet Seat	(As S036)	3 Num	No Further Action Required
<u>► \$059</u>	Management	Main, Ground, 021 Classroom, Walls & Floor, Walls & Floor		Num	No further action required
<u>▶ \$061</u>	Management	Main, Ground, 022 Boys Toilets, Walls Internal, Walls Internal		Num	No further action required
<u>► 5064</u>	Management	Main, Ground, 023 Cloaks, Walls Internal, Walls Internal		Num	No further action required
▶ \$067	Management	Main, Ground, 024 Classroom, Walls & Floor, Walls & Floor		Num	No further action required
<u>► S069</u>	Management	Main, Ground, 026 Covered Play Area, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
<u>► 5071</u>	Management	Main, Ground, 027 Girls Toilets, Walls Internal, Walls Internal		Num	No further action required
► S073	Management	Main, Ground, 027 Girls Toilets, Toilet Seat, Toilet Seat	(As S036)	3 Num	No Further Action Required
E	1				

▶ 5075	Management	Main, Ground, 028 Classroom, Walls & Floor, Walls & Floor		Num	No further action required
► S077	Management	Main, Ground, 029 Female Toilets, Ceiling & Walls, Ceiling & Walls		Num	No further action required
<u>► 5080</u>	Management	Main, Ground, 030 Head Teachers Office, Walls Internal, Walls Internal		Num	No further action required
► S083	Management	Main, Ground, 031 Staff Room, Walls & Floor, Walls & Floor		Num	No further action required
<u>► 5085</u>	Management	Main, Ground, 031A Passage, Ceiling, Ceiling	S085	8 Sqr Mtrs	No Further Action Required
<u>> 5086</u>	Management	Main, Ground, 031A Passage, Walls & Floor, Walls & Floor		Num	No further action required
<u>► 5087</u>	Management	Main, Ground, 032 Site Managers Room, Ceiling, Ceiling	(As S085)	8 Sqr Mtrs	No Further Action Required
<u>➤ 5088</u>	Management	Main, Ground, 032 Site Managers Room, Walls Internal, Walls Internal		Num	No further action required
<u>► 5090</u>	Management	Main, Ground, 033 Store Room, Ceiling, Ceiling	(As S085)	4 Sqr Mtrs	No Further Action Required
<u>► 5091</u>	Management	Main, Ground, 033 Store Room, Walls Internal, Walls Internal		Num	No further action required
<u>► \$093</u>	Management	Main, Ground, 034 First Aid Room, Ceiling & Walls, Ceiling & Walls		Num	No further action required
<u>► \$096</u>	Management	Main, Ground, 035 Wet Room, Ceiling, Ceiling	(As S085)	9 Sqr Mtrs	No Further Action Required
►S097	Management	Main, Ground, 035 Wet Room, Walls Internal, Walls Internal		Num	No further action required
<u>▶ \$100</u>	Management	Main, Ground, 076 Reprographics , Walls Internal, Walls Internal		Num	No further action required
<u>►5102</u>	Management	Main, Ground, 036 Junior Hall, Ceiling, Ceiling	(As S085)	250 Sqr Mtrs	No Further Action Required
<u>►S103</u>	Management	Main, Ground, 036 Junior Hall, Walls & Floor, Walls & Floor		Num	No further action required
1	3				

					3
<u>► \$105</u>	Management	Main, Ground, 075 PE Store, Ceiling, Ceiling	(As S085)	16 Sqr Mtrs	No Further Action Required
►S106	Management	Main, Ground, 075 PE Store, Walls Internal, Walls internal		Num	No further action required
<u>▶ \$108</u>	Management	Main, Ground, 037 Servery / Chair Store, Ceiling & Walls, Ceiling & Walls		Num	No further action required
<u>►S111</u>	Management	Main, Ground, 052 Wash Up Area, Ceiling, Textured Coating To Ceiling	S111	20 Sqr Mtrs	No Further Action Required
<u>►S112</u>	Management	Main, Ground, 052 Wah Up Area, Walls & Floor, Walls & Floor		Num	No further action required
<u>►S113</u>	Management	Main, Ground, 038 Kitchen, Ceiling, Textured Coating To Ceiling	(As S111)	60 Sqr Mtrs	No Further Action Required
<u>▶ S114</u>	Management	Main, Ground, 038 Kitchen , Walls & Floor, Walls & Floor		Num	No further action required
<u>▶ \$115</u>	Management	Main, Ground, 038 Kitchen , Sink Pad, Sink Pad	S115	2 Num	No Further Action Required
<u>►S118</u>	Management	Main, Ground, 039 & 040 Fire Exit, Ceiling, Textured Coating To Ceiling	(As S111)	18 Sqr Mtrs	No Further Action Required
<u>► 5119</u>	Management	Main, Ground, 039 & 040 Fire Exit, Walls & Floor, Walls & Floo	r	Num	No further action required
►S120	Management	Main, Ground, 039 & 040 Fire Exit, Consumer Unit, Consumer Unit		Num	No further action required
►S123	Management	Main, Ground, 041 Kitchen Office , Walls & Floor, Walls & Floo	r	Num	No further action required
<u>►S124</u>	Management	Main, Ground, 042 Cupboard, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
<u>►S125</u>	Management	Main, Ground, 044 Cleaners Cupboard, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
►S127	Management	Main, Ground, 045 Kitchen Toilet, Walls & Floor, Walls & Floor		Num	No further action required
	F				

				· · · · · · · · · · · · · · · · · · ·	
<u>► \$128</u>	Management	Main, Ground, 045 Kitchen Toilet, Toilet Seat, Toilet Seat	(As S036)	1 Num	No Further Action Required
<u>▶\$130</u>	Management	Main, Ground, 046 Changing Room, Walls & Floor, Walls & Floor		Num	No further action required
<u>►S131</u>	Management	Main, Ground, 048 Kitchen Store, Ceiling, Textured Coating To Ceiling	(As S111)	20 Sqr Mtrs	No Further Action Required
<u>► \$132</u>	Management	Main, Ground, 048 Kitchen Store, Walls & Floor, Walls & Floor		Num	No further action required
<u>►S133</u>	Management	Main, Ground, 050 Small Kitchen, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
<u>►S134</u>	Management	Main, Ground, 051 Classroom , Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
►S136	Management	Main, Ground, 051A Resource Room, Ceiling, Ceiling	(As S085)	4 Sqr Mtrs	No Further Action Required
<u>►5137</u>	Management	Main, Ground, 051A Resource Room, Walls & Floor, Walls & Floor		Num	No further action required
<u>►S138</u>	Management	Main, Ground, 053 Lobby 1, Ceiling, Ceiling	S138	18 Sqr Mtrs	No Further Action Required
<u>►\$139</u>	Management	Main, Ground, 053 Lobby 1, Walls Internal, Walls Internal		Num	No further action required
<u>▶ 5141</u>	Management	Main, Ground, 054 Resource Area, Ceiling, Ceiling	(As S138)	60 Sqr Mtrs	No Further Action Required
<u>►S142</u>	Management	Main, Ground, 054 Resource Area, Walls Internal, Walls Internal		Num	No further action required
<u>▶5144</u>	Management	Main, Ground, 055 Classroom , Ceiling, Ceiling	(As S138)	60 Sqr Mtrs	No Further Action Required
<u>►\$145</u>	Management	Main, Ground, 055 Classroom, Walls Internal, Walls Internal		Num	No further action required
►S147	Management	Main, Ground, 056 Girls Toilets, Ceiling, Ceiling	(As S138)	9 Sqr Mtrs	No Further Action Required
<u>► S148</u>	Management	Main, Ground, 056 Girls Toilets, Walls Internal, Walls Internal		Num	No further action required
	1100		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	1	

			.,		
<u>▶ \$150</u>	Management	Main, Ground, 057 & 58 Classroom Store, Ceiling, Ceiling	(As S138)	1 Sqr Mtrs	No Further Action Required
<u>▶\$151</u>	Management	Main, Ground, 057 & 058 Classroom Store, Walls Internal, Walls Internal		Num	No further action required
<u>►S153</u>	Management	Main, Ground, 059 Classroom, Ceiling, Ceiling	(As S138)	60 Sqr Mtrs	No Further Action Required
▶ \$154	Management	Main, Ground, 059 Classroom, Walls Internal, Walls Internal		Num	No further action required
<u>► 5156</u>	Management	Main, Ground, 060 Classroom Store, Ceiling, Ceiling	(As S138)	1 Sqr Mtrs	No Further Action Required
<u>► S157</u>	Management	Main, Ground, 060 Classroom Store, Walls Internal, Walls Internal		Num	No further action required
▶ S159	Management	Main, Ground, 061 Cloaks, Ceiling, Ceiling	(As S138)	12 Sqr Mtrs	No Further Action Required
►S160	Management	Main, Ground, 061 Cloaks, Walls Internal, Walls Internal		Num	No further action required
<u>►S162</u>	Management	Main, Ground, 062 Boys Toilets, Ceiling, Ceiling	(As S138)	9 Sqr Mtrs	No Further Action Required
►S163	Management	Main, Ground, 062 Boys Toilets, Walls Internal, Walls Internal		Num	No further action required
<u>► \$165</u>	Management	Main, Ground, 063 ICT Suite, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
<u>►S166</u>	Management	Main, Ground, 064 ICT Server Room, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
<u>▶S167</u>	Management	Main, Ground, 065 Girls Toilets, Ceiling, Ceiling	(As S138)	9 Sqr Mtrs	No Further Action Required
►S168	Management	Main, Ground, 065 Girls Toilets, Walls Internal, Walls Internal		Num	No further action required
<u>►\$170</u>	Management	Main, Ground, 066 Resource Area, Ceiling, Ceiling	(As S138)	60 Sqr Mtrs	No Further Action Required
►S171	Management	Main, Ground, 066 Resource Area, Walls Internal, Walls Internal		Num	No further action required

					S
► S173	Management	Main, Ground, 067 Cloaks, Ceiling, Ceiling	(As S138)	12 Sgr Mtrs	No Further Action Required
<u>►S174</u>	Management	Main, Ground, 067 Cloaks, Walls Internal, Walls Internal		Num	No further action required
<u>► \$176</u>	Management	Main, Ground, 068 Classroom, Ceiling, Ceiling	(As S138)	60 Sqr Mtrs	No Further Action Required
<u>► S177</u>	Management	Main, Ground, 068 Classroom, Walls Internal, Walls Internal		Num	No further action required
▶ S179	Management	Main, Ground, 069 Classroom Store, Ceiling, Ceiling	(As S138)	1 Sqr Mtrs	No Further Action Required
<u>►5180</u>	Management	Main, Ground, 069 Classroom Store, Walls Internal, Walls Internal		Num	No further action required
<u>► S182</u>	Management	Main, Ground, 070 Classroom Store, Ceiling, Ceiling	(As S138)	1 Sqr Mtrs	No Further Action Required
►S183	Management	Main, Ground, 070 Classroom Store, Walls Internal, Walls Internal		Num	No further action required
<u>► S185</u>	Management	Main, Ground, 071 Classroom, Ceiling, Ceiling	(As S138)	60 Sqr Mtrs	No Further Action Required
<u>►S186</u>	Management	Main, Ground, 071 Classroom, Walls Internal, Walls Internal		Num	No further action required
<u>►S188</u>	Management	Main, Ground, 072 Boys Toilets, Ceiling, Ceiling	(As S138)	9 Sqr Mtrs	No Further Action Required
►S189	Management	Main, Ground, 072 Boys Toilets, Walls Internal, Walls Internal		Num	No further action required
►S191	Management	Main, Ground, 073 & 074 Reading Area, Ceiling, Ceiling	(As S138)	60 Sqr Mtrs	No Further Action Required
<u>►S192</u>	Management	Main, Ground, 073 & 074 Reading Area, Walls & Floor, Walls & Floor		Num	No further action required
► S193	Management	Main, Ground, 077 & 088 Entrance Lobby, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
<u>► \$194</u>	Management	Main, Ground, 078 Meeting Room, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required

				5
► S195	Management	Main, Ground, 069 Office, Ceiling, Walls & Floor, Ceiling, Walls & Floor	Num	No further action required
►S196	Management	Main, Ground, 080 Server Room, Ceiling, Walls & Floor, Ceiling, Walls & Floor	Num	No further action required
►S197	Management	Main, Ground, 081 Classroom, Ceiling, Walls & Floor, Ceiling, Walls & Floor	Num	No further action required
►S198	Management	Main, Ground, 082 Kitchen, Ceiling, Walls & Floor, Ceiling, Walls & Floor	Num	No further action required
<u>▶ S199</u>	Management	Main, Ground, 083 Toilets , Ceiling, Walls & Floor, Ceiling, Walls & Floor	Num	No further action required
<u>► \$200</u>	Management	Main, Ground, 084 Corridor / Cloaks, Ceiling, Walls & Floor, Ceiling, Walls & Floor	Num	No further action required
<u>►5201</u>	Management	Main, Ground, 085 Toilet, Ceiling, Walls & Floor, Ceiling, Walls & Floor	Num	No further action required
► S202	Management	Main, Ground, 086 Disabled Toilet, Ceiling, Walls & Floor, Ceiling, Walls & Floor	Num	No further action required
► \$203	Management	Main, Ground, 087 Plant Room, Ceiling, Walls & Floor, Ceiling, Walls & Floor	Num	No further action required
<u>► S205</u>	Management	Main, Ground, N001 Cloakroom, Walls Internal, Walls Internal	Num	No further action required
<u>▶ \$208</u>	Management	Main, Ground, N001A Disabled Toilet, Walls Internal, Walls Internal	Num	No further action required
<u>► 5211</u>	Management	Main, Ground, N002 Nursery Classroom, Walls & Floor, Walls & Floor	Num	No further action required
<u>►S213</u>	Management	Main, Ground, N004 Toilets, Ceiling, Walls & Floor, Ceiling, Walls & Floor	Num	No further action required

1209920 - Page **24** of **147**

<u>► \$214</u>	Management	Main, Ground, N005 Sand Pit, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
<u>▶S215</u>	Management	Main, Ground, N006 Store Room, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
<u>►S216</u>	Management	Main, Ground, N006A Covered Play Area, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
<u>►S218</u>	Management	Main, Ground, N007 Laundry , Walls Internal, Walls Internal	,	Num	No further action required
<u>► \$221</u>	Management	Main, Ground, N007A Laundry Store, Walls Internal, Walls Internal		Num	No further action required
▶ \$223	Management	Main, First, 101 Stairwells, Ceiling, Ceiling	S223	6 Sqr Mtrs	No Further Action Required
<u>▶ 5224</u>	Management	Main, First, 101 Stairwells, Walls & Floor, Walls & Floor		Num	No further action required
<u>▶5225</u>	Management	Main, First, 102 Lobby / Cloaks, Ceiling, Ceiling	(As 5223)	10 Sqr Mtrs	No Further Action Required
►S226	Management	Main, First, 102 Lobby / Cloaks, Walls Internal, Walls Internal		Num	No further action required
<u>►5228</u>	Management	Main, First, 103 Girls Toilets, Ceiling & Walls, Ceiling & Walls		Num	No further action required
►S230	Management	Main, First, 103 Girls Tollets, Tollet Seat, Tollet Seat	S230	3 Num	No Further Action Required
<u>► S231</u>	Management	Main, First, 104 Resource Area, Ceiling, Ceiling	(As S223)	60 Sgr Mtrs	No Further Action Required
<u>► S232</u>	Management	Main, First, 104 Resource Area, Walls Internal, Walls Internal		Num	No further action required
<u>▶ 5234</u>	Management	Main, First, 105 Cleaners Store, Ceiling, Ceiling	(As S223)	1 Sqr Mtrs	No Further Action Required
► S235	Management	Main, First, 105 Cleaners Store, Walls Internal, Walls Internal		Num	No further action required
►S237	Management	Main, First, 106 Classroom Store, Ceiling, Ceiling	(As S223)	1 Sqr Mtrs	No Further Action Required
<u>► 5238</u>	Management	Main, First, 106 Classroom Store, Walls Internal, Walls Internal		Num	No further action required
1	ł				

J209920 - Page **25** of **147**

1209920-26/08/2022 STHMBC

					Ş
► S240	Management	Main, First, 107 Classroom, Ceiling, Ceiling	(As S223)	60 Sqr Mtrs	No Further Action Required
▶ 5241	Management	Main, First, 107 Classroom, Walls Internal, Walls Internal		Num	No further action required
<u>► 5243</u>	Management	Main, First, 108 Classroom, Ceiling, Ceiling	(As S223)	60 Sqr Mtrs	No Further Action Required
▶ \$244	Management	Main, First, 108 Classroom, Walls Internal, Walls Internal		Num	No further action required
► S246	Management	Main, First, 109 Classroom Cupboards, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
<u>► 5247</u>	Management	Main, First, 110 Cloaks, Ceiling, Ceiling	(As S223)	12 Sqr Mtrs	Na Further Action Required
► S248	Management	Main, First, 110 Cloaks, Walls Internal, Walls Internal		Num	No further action required
<u>► \$250</u>	Management	Main, First, 111 Boys Toilets, Ceiling & Walls, Ceiling & Walls		Num	No further action required
<u>▶\$252</u>	Management	Main, First, 111 Boys Tollets, Toilet Seat, Toilet Seat	(As S230)	1 Num	No Further Action Required
<u>► \$253</u>	Management	Main, First, 112 & 113 Resource Area, Ceiling, Ceiling	(As S223)	60 Sqr Mtrs	No Further Action Required
<u>►5254</u>	Management	Main, First, 112 & 113 Resource Area , Walls Internal, Walls Internal		Num	No further action required
<u>► \$256</u>	Management	Main, First, 114 Store, Ceiling, Ceiling	(As S223)	6 Sqr Mtrs	No Further Action Required
► S257	Management	Main, First, 114 Store, Walls & Floor, Walls & Floor		Num	No further action required
►S258	Management	Main, First, 115 Lobby / Cloaks, Ceiling, Ceiling	(As S223)	10 Sqr Mtrs	No Further Action Required
<u>▶ \$259</u>	Management	Main, First, 115 Lobby / Cloaks, Walls Internal, Walls Internal		Num	No further action required
► <u>\$261</u>	Management	Main, First, 116 Resource Area , Ceiling, Ceiling	(As \$223)	60 Sqr Mtrs	No Further Action Required
<u>▶ \$262</u>	Management	Main, First, 116 Resource Area, Walls Internal, Walls Internal		Num	No further action required

					5
<u>▶S264</u>	Management	Main, First, 117 Girls Toilets, Ceiling & Walls, Ceiling & Walls		Num	No further action required
<u>► \$266</u>	Management	Main, First, 118 Cloaks, Ceiling, Ceiling	(As S223)	12 Sqr Mtrs	No Further Action Required
<u>▶ \$267</u>	Management	Main, First, 118 Cloaks, Walls Internal, Walls Internal		Num	No further action required
<u>▶\$269</u>	Management	Main, First, 119 Classroom, Ceiling, Ceiling	(As S223)	60 Sqr Mtrs	No Further Action Required
<u>►5270</u>	Management	Main, First, 119 Classroom, Walls Internal, Walls Internal		Num	No further action required
<u>► \$272</u>	Management	Main, First, 120 Classroom Cupboards, Ceiling, Walls & Floor, Ceiling, Walls & Floor		Num	No further action required
► S273	Management	Main, First, 121 Classroom , Ceiling, Ceiling	(As 5223)	60 Sqr Mtrs	No Further Action Required
► S274	Management	Main, First, 121 Classroom, Walls Internal, Walls Internal		Num	No further action required
<u>►S276</u>	Management	Main, First, 122 Classroom Store, Ceiling, Ceiling	(As S223)	1 Sqr Mtrs	No Further Action Required
<u>► \$277</u>	Management	Main, First, 122 Classroom Store, Walls Internal, Walls Internal	1	Num	No further action required
► \$279	Management	Main, First, 123 Small Store, Ceiling, Ceiling	(As S223)	1 Sqr Mtrs	No Further Action Required
► S280	Management	Main, First, 123 Small Store, Walls Internal, Walls Internal		Num	No further action required
<u>►S282</u>	Management	Main, First, 124 Boys Toilets, Ceiling & Walls, Ceiling & Walls		Num	No further action required
<u>► 5284</u>	Management	Main, First, 124 Boys Toilets, Toilet Seat, Toilet Seat	(As S230)	1 Num	No Further Action Required
<u>► \$286</u>	Management	Main, Ground, 007 Gas Meter Cupboard , Walls & Floor, Walls & Floor		Num	No further action required
►S288	Management	Main, Ground, 008 Boiler Room , Walls & Floor, Walls & Floor		Num	No further action required
<u>► \$289</u>	Management	Main, Ground, 008 Boiler Room , Pipework, Gaskets	S289	4 Num	No Further Action Required
1					

Num No further action required Main, Ground, 008 Boiler Room , Live Plant, Plant Equipment **▶** 5290 Management Main, Ground, 043 External Store, Celling, Walls & Floor, Num No further action required <u>► S292</u> Management Ceiling, Walls & Floor Main, Ground, 047 Main Switch Room, Ceiling, Walls & Floor, Num No further action required <u>► 5293</u> Management Ceiling, Walls & Floor No further action required Main, Ground, 047 Main Switch Room, Electric Meter & Num <u>▶ 5294</u> Management Consumer Unit, Electric Meter & Consumer Unit No Further Action Required 15 Sqr Mtrs Main, Ground, 049 Boiler Room 2, Ceiling, Ceiling S296 ➤ S2<u>96</u> Management 10 Num No Further Action Required (As S289) Main, Ground, 049 Boiler Room 2, Pipework, Gaskets ►S298 Management No further action required Num Main, Ground, 049 Boiler Room 2, Live Plant, Plant Equipment **►**5299 Management No Further Action Required Main, Ground, 049 Boiler Room 2, Insulation Debris / Residues, S300 40 Sqr Mtrs <u>▶ 5300</u> Management All Surfaces Main, External, All Elevations, Roof, Walls External & Rain Num No further action required <u>► S303</u> Management Water Goods, Roof, Walls External & Rain Water Goods

Site Specific Areas of No Access ◀ Back

The following areas were not accessed and need to be incorporated within the Management Plan and/or inspected during the re-inspection campaign, see Section 3 – Site Specific Information – Additional Notes for further information.

Record ID	Location	No Access Justification
<u>▶5002</u>	Main, Ground.	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for
	001 Main Entrance Lobby,	details.
	Behind Cladding	
> 007	Main,	Access was denied on the day of survey – see Inspection
<u>▶S007</u>	Ground,	Comments (Material & Priority Assessment Records) for
	004 Corridor,	details.
	Behind Cladding	
> 5025	Main,	Access was denied on the day of survey – see Inspection
<u>▶ \$035</u>	Ground,	Comments (Material & Priority Assessment Records) for
	013 Girls Toilets,	details.
	Below Floor Covering	
▶ S039	Main,	Access was denied on the day of survey – see Inspection
3039	Ground,	Comments (Material & Priority Assessment Records) for
	014 Cloaks.	details.
	Below Floor Covering	
▶ S042	Main,	Access was denied on the day of survey – see Inspection
3042	Ground,	Comments (Material & Priority Assessment Records) for
	015 Classroom,	details.
	Behind Boxing	
▶S046	Main,	Access was denied on the day of survey – see Inspection
- 3010	Ground,	Comments (Material & Priority Assessment Records) for
	017 Boys Toilets,	details.
	Below Floor Covering	
►S050	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	018 Classroom,	details.
	Behind Boxing	
►S053	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	019 Cloaks,	details.

J209920 - Page 29 of 147

	Below Floor Covering	
<u>▶ \$056</u>	Main, Ground, O20 Girls Toilets, Below Floor Covering	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.
<u>▶5062</u>	Main, Ground, O22 Boys Toilets, Below Floor Covering	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.
<u>▶5065</u>	Main, Ground, 023 Cloaks, Below Floor Covering	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.
8002 €	Main, Ground, 024 Classroom, Behind Boxing	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.
<u>▶5072</u>	Main, Ground, 027 Girls Toilets, Below Floor Covering	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.
<u>▶5076</u>	Main, Ground, 028 Classroom, Behind Boxing	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.
<u>▶</u> 5078	Main, Ground, 029 Female Toilets, Below Floor Covering	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.
<u>▶</u> 5084	Main, Ground, 031 Staff Room, Behind Boxing	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.
<u>►S089</u>	Main, Ground, 032 Site Managers Room, Below Floor Covering	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.

J209920 - Page **30** of **147**

J209920-26/08/2022

▶S094	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	034 First Aid Room,	details.
	Below Floor Covering	
<u>> S098</u>	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	035 Wet Room,	details.
	Below Floor Covering	
<u>S101</u>	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	076 Reprographics ,	details.
	Below Floor Covering	
►S104	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	036 Junior Hall,	details.
	Behind Cladding	
►S109	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	037 Servery / Chair Store,	details.
	Below Floor Covering	
►S117	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	052 Wash Up Area,	details.
	Behind Boxing	
►S121	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
039 & 040 Fire Exit , details Behind Boxing	details.	
	Behind Boxing	
►S122	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records)
	041 Kitchen Office,	details.
	Above Ceiling	
S126	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	045 Kitchen Toilet,	details.
	Above Ceiling	

J209920 - Page 31 of 147

▶S129	Main.	Access was denied on the day of survey – see Inspection
<u> </u>	Ground,	Comments (Material & Priority Assessment Records) for
	046 Changing Room,	details.
	Above Ceiling	
►S135	Main.	Access was denied on the day of survey – see Inspection
3133	Ground,	Comments (Material & Priority Assessment Records) for
	051 Classroom.	details.
	Behind Boxing	
C140	Main,	Access was denied on the day of survey – see Inspection
<u>► \$140</u>	Ground,	Comments (Material & Priority Assessment Records) for
		details.
	053 Lobby 1,	
	Below Floor Covering	
<u>▶S143</u>	Main,	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for
	Ground,	details.
	054 Resource Area,	
	Below Floor Covering	
<u>► \$149</u>	Main,	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for
	Ground,	details.
	056 Girls Toilets,	uctons.
	Below Floor Covering	
<u>►S161</u>		Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for details.
	061 Cloaks,	details.
	Below Floor Covering	
►S164	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	062 Boys Toilets,	details.
	Below Floor Covering	
<u>>\$169</u>	Main,	Access was denied on the day of survey – see Inspection
	1 Ground,	Comments (Material & Priority Assessment Records) for
	065 Girls Toilets,	details.
	Below Floor Covering	
►S172	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	066 Resource Area, details.	details.
	Below Floor Covering	

J209920 - Page 32 of 147

		STHMBO
<u>▶S175</u>	Main,	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for
	Ground,	details.
	067 Cloaks,	uctais.
	Below Floor Covering	
<u>▶\$190</u>	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	072 Boys Toilets,	details.
	Below Floor Covering	
▶S206	Main,	Access was denied on the day of survey – see Inspection
	Ground.	Comments (Material & Priority Assessment Records) for
	N001 Cloakroom,	details.
	Below Floor Covering	
►S209	Main,	Access was denied on the day of survey – see Inspection
3205	Ground,	Comments (Material & Priority Assessment Records) for
	N001A Disabled Toilet,	details.
	Below Floor Covering	
b.co42		Access was denied on the day of survey – see Inspection
<u>▶S212</u>	Main,	Comments (Material & Priority Assessment Records) for
	Ground, N003 Store Room,	details.
	[1] [1] [1] [1] [1] [1] [1] [1] [1] [1]	
	No Access	A service desired on the day of supray, see Inspection
<u>▶S219</u>	Main,	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for
	Ground,	details.
	N007 Laundry,	actoris,
	Below Floor Covering	
<u>▶S222</u>	Main,	Access was denied on the day of survey – see Inspection
	Ground,	Comments (Material & Priority Assessment Records) for
	N007A Laundry Store,	details.
	Below Floor Covering	
►S227	Main,	Access was denied on the day of survey – see Inspection
	First,	Comments (Material & Priority Assessment Records) for
	102 Lobby / Cloaks,	details.
	Below Floor Covering	
<u>►5229</u>	Main,	Access was denied on the day of survey – see Inspection
	First,	Comments (Material & Priority Assessment Records) for
	103 Girls Toilets,	details.
	Below Floor Covering	
	Delow Floor Covering	

J209920 - Page **33** of **147**

<u>▶S233</u>	Main,	Access was denied on the day of survey – see Inspection
	First,	Comments (Material & Priority Assessment Records) for
	104 Resource Area ,	details.
	Below Floor Covering	
►S236	Main,	Access was denied on the day of survey – see Inspection
	First,	Comments (Material & Priority Assessment Records) for
	105 Cleaners Store,	details.
	Below Floor Covering	
►S249	Main,	Access was denied on the day of survey – see Inspection
	First,	Comments (Material & Priority Assessment Records) for
	110 Cloaks,	details.
	Below Floor Covering	
▶S251	Main,	Access was denied on the day of survey – see Inspection
	First,	Comments (Material & Priority Assessment Records) for
	111 Boys Toilets,	details.
	Below Floor Covering	
► S255	Main,	Access was denied on the day of survey – see Inspection
	First,	Comments (Material & Priority Assessment Records) for
	112 & 113 Resource Area,	details.
	Below Floor Covering	
►S260	Main,	Access was denied on the day of survey – see Inspection
	First,	Comments (Material & Priority Assessment Records) for
	115 Lobby / Cloaks,	details.
	Below Floor Covering	
► S263	Main,	Access was denied on the day of survey – see Inspection
	First,	Comments (Material & Priority Assessment Records) for
	116 Resource Area ,	details.
	Below Floor Covering	
<u>►S265</u>	Main,	Access was denied on the day of survey – see Inspect
	First,	Comments (Material & Priority Assessment Records) for
	117 Girls Toilets,	details.
	Below Floor Covering	
▶S268	Main,	Access was denied on the day of survey – see Inspection
	First,	Comments (Material & Priority Assessment Records) for details.
	118 Cloaks,	details.
	Below Floor Covering	

J209920 - Page **34** of **147**

<u>▶5281</u>	Main, First, 123 Small Store, Below Floor Covering	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.
<u>►5283</u>	Main, First, 124 Boys Toilets, Below Floor Covering	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.
<u>►5291</u>	Main, Ground, 008 Boiler Room , Floor Void	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.
<u>▶5301</u>	Main, External, All Elevations, Behind Fascias	Access was denied on the day of survey – see Inspection Comments (Material & Priority Assessment Records) for details.
<u>▶5302</u>	Main, External, Roof, No Access	A risk assessment identified high risk exposure to the surveyor, normally due to high voltage, height or other hazardous risks being present.